SHIMOGA DIVISION.

Notifications dated 1st August 1905.

1. The attention of the public is invited to the Notification dated 25th July 1905 calling for tender for constructing a new tank at Sowlunga in Honnali Taluk.

2. The attention of the public is invited to the Notification dated 25th July 1905 calling for tenders for extending Avinahalli-Karur road from Hurli stream to the Ghat road at Kogarur in Sagar Taluk.

K. KRISHNAIENGAR,
Executive Engineer.

CHITALDRUG DIVISION.

Dated 13th August 1905.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 5th September 1905, for restoring the Dummi Tank, Registered No. 140, Holalkere Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1906.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 (one hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Dummi Tank, Registered No. 140, Holalkere Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Detailed abstract estimate showing the quantities of resorting Dummi Tank, Registered No. 140 of Holalkere Taluk.

Items of work.

	Per	*Quantity.*
Bund 55·00 top width 6′ and jack bund 4′.		
Earthwork to bund (Bed stuff	C. yd.	7,363
Gravelly soil to be mixed with the bed stuff (as per Chief Engineer's order) including gravel backing.	Do	8,119
New stone work	Do	3,035
Old stone work	Do	2,115
Grade stones with bed slabs	No.	59
B. M. Stones	Do	2
Gauge stone	Do	1
Regd. No. stone	Do	1
Top width stones	Do	59
Jungle clearing	Lump sum	Rs.
Earthwork cut opening and refilling over revetment	C. yd.	93
Turfing	Sq. yd.	7,949
Stone pitching	Do	1,445
Right waste-weir 130′ feet long and R. L. 50·00.		
Earthwork, excavation and to be used to bund	C. yd.	435
Burnt brick in surki mortar	C. ft.	1,364
Burnt stone slabs	Sq. ft.	549
Rough plastering	Sqrs.	13·38
Fine plastering	Do	1·72
Rough stone work, new	C. yd.	295
Old stone work	Do	40
Cutting joints of slabs	Each.	As per measurements.